

7-2

4-032242

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-109-20,477-0000

SE SE NE / 4 SEC. 29, 15, 35 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 5140

Lease: Linder Well # 1

Operator: Frontier Oil Company

County: Logan 154.05

Address: 125 N. Market - Suite #1720  
Wichita, Kansas 67202

Well total depth 4740 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 374 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License#

Address: Oakley, Kansas 67748

Company to plug at: Hour: A.M. Day: 2 Month: July Year: 1997

Plugging proposal received from: Dick Parker

Company: Frontier Oil Company Phone:

Were: Order 240 sxs 60/40 pozmix - 10% gel - 300# hulls.

7-15-97  
11:55  
A 11:55

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:45 A.M., Day: 2 Month: July Year: 1997

Actual plugging report: 8 5/8" set at 374' w/210 sxs cwc. 4 1/2" set at 4492' with 225 sxs. Prod. Perf. 3980' - 3982'. Squeezed 4 1/2" with 180 sxs 60/40 pozmix - 10% gel - 300# hulls. Max. P.S.I. 500#. S.I.P. 200#. Squeezed 8 5/8" with 20 sxs cement blend to 300#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

INVOICED

10

DATE 10/7  
485-44  
7-2