

6 031452

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-109-20485-0000

50' E of, SEC. 29, T 15 S, R 35 W/EX  
NW NE SE  
2310 feet from S section line  
940 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: Frontier Oil Co.  
Name & Address: 125 N. Market Suite 1720  
Wichita, Ks. 67202

Lease Name Dirks Well # 4  
County LogAN 146.12  
Well Total Depth 4496 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Co. License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 15 Month: Nov Year: 19 90

Plugging proposal received from Dick Parker

(company name) Frontier (phone)

were: 8 5/8 set at 365 w/365 sks. 4 1/2 set at 4491 w/225 sks. PRTD 4440

Perf 3970 - 4240. Shot holes at 2450. Recovered pipe w/shot at 1525.

Order 250 sks 65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co. Walker Water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:45PM Day: 15 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 2900 - Left bailer stuck in sand.

Bailed 4 sks common cement on sand and stuck bailer w/new bailer. Recovered 1525 of 4 1/2

casing. Sq 8 5/8 w/250 sks cement blend w/500 lbs. hulls. Mixed into max psi 800 lbs.

Close in psi 300 lbs. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 28 1990 11-28-90

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-90

NO. 30149

J.H.S.

Signed Carl Goodrow  
(TECHNICIAN)