

6-23

4-041700

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20, 229-60-60

E2 SE NW / 4 SEC. 30, 14 S, 40 W
3300 feet from S section line
2310 feet from W section line

Operator license# 4779 Lease: Coker Well # 30-1

Operator: North American Resources Co. County: Wallace 170.63

Address: 1700 Broadway Suite #508 Denver, CO 80290
Well total depth 5250 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 413 feet
W/275 sxs.

Aband. Oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie License# 30684

Address:

Company to plug at: Hour: P.M. Day: 23 Month: June Year: 1995

Plugging proposal received from: Walter Brown

Company: Abercrombie Phone:

Were: Order 200 sxs. 60/40 posmix - 6% gel with 1/4# F.C. per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: P.M. Day: 23 Month: June

RECEIVED 1995
STATE CORPORATION COMMISSION

Actual plugging report:

- 1st. Plug at 2760' with 25 sxs.
- 2nd. Plug at 1780' with 100 sxs.
- 3rd. Plug at 460' with 40 sxs.
- 4th. Plug at 40' with 10 sxs.
- 15 sxs in rathole.
- 10 sxs in mousehole

JUL 28 1995
07-28-95
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO X
Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

DATE 7-28-95

INV. N. 43197

Dennis L. Hamel
(agent)