

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-053-20607-00-00

SE, Sec. 17, T 14 S, R 10 (W)

1980 feet from (S) section line

2310 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name ZBORNIK Well # 1-17

Operator: Kelso Casing Pulling  
Name & Address P.O. Box 347  
Chase, Kansas 67524

County Ellsworth

Well Total Depth 75.63 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 3/8 feet 406

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050 Rig # 1674

Address P.O. Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:00 A Day: 25 Month: June Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) 316 938 2320

were: (Well-Dead) Fill hole with sand to 2075 and cement with 4 sacks cement w/dump bailers Squeeze hole with 4 sacks hulls, 15 sacks Bentonite, 30 sacks 50/50 Permox w/4% gel, 5 sacks Bentonite 1 sack hulls, 8 3/8" plug, and 125 sacks 50/50 Permox w/4% gel. Pump into 8 3/8" surface casing.

Signed (Signature)  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 A Day: 25 Month: June Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with sand to 2075' and 5 sacks cement dumped on sand with dump bailers. Hole squeezed with 4 sacks hulls 15 sacks gel (Bentonite), 30 sacks 50/50 Permox w/4% gel, 5 sacks gel (Bentonite), 8 3/8" plug, and 125 sacks 50/50 Permox w/4% gel. pumped into 8 3/8" surface casing.

Remarks: 1324' of 4 1/2" casing recovered Max press. 600 PSI Close in 200 PSI

Allied Cementing Co., Inc. Ticket # 37509

4 1/2" - 2324-150 sacks Top Ref 2134

I hereby certify that the above plugging instructions were given as herein stated and that I (did) / ~~did not~~ observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

7-12-84  
2420

JUL 06 1984  
07-06-84  
CONSERVATION DIVISION  
Wichita, Kansas

Signed (Signature)  
(TECHNICIAN)