

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00505-00-01
Spot: SWNW Sec/Twnshp/Rge: 27-28S-7W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: ALAMEDA UNIT OWWO Well #: 6-3
County: KINGMAN Total Vertical Depth: 4444 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC. DBA CRYSTAL R
Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		240 SX
PROD	4.5	4443		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2010 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: JIM KRAFT Company: _____ Phone: (620) 388-2356

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/05/2010 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

9/22/10 PERF CASING @ 2500' --1075'--675' GAS BLEW THE GUN UP TO ABOUT 270' AND CUT WIRELINE, GASSED UP CASING FORCED PACKER IN CASING TO SHUT GAS OFF, SWEDGED UP. 9/24/10 FISHED MULTI-GUN AND CABLE OUT OF HOLE. 50 SX @ 2500' 50 SX @ 1075 -- 50 SX @ 675' TAGGED TOP OF CEMENT AT 650' -- 60 SX @ 315'-- 10-5-10 CUT HEAD OFF AND RAN 150' OF ONE INCH WITH 70 SX OF CEMENT BETWEEN 4.5 AND 8.625--DONE AT 10:00 AM.-CHECKED CEMENT AT 2:30 PM EVERYTHING STILL FULL. COMMISSION ORDER REQUIRING WELL BORE TO BE PLUGGED, JUNK IN HOLE, PAST 10 YEAR NON-PRODUCER.

Perfs:

Top	Bot	Thru	Comments
4385	4388		SIMP.
4371	4375		VIOLA
4364	4366		VIOLA
3992	3996		MISSISSIPPI
3703	3708		LKC

RECEIVED
AUG 29 2011
KCC WICHITA

Remarks: ALLIED CEMENTING OUT OF MEDICINE LODGE, KS TICKET #41404-- COMMON CEMENT USED FOR PLUGGING JOB.

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)