

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22378-00-00  
Spot: S2SESE Sec/Twnshp/Rge: 10-6S-21W  
330 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HELEN HOLMQUIST Well #: 3  
County: GRAHAM Total Vertical Depth: 3793 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	253	0	165 sx
PROD	4.5	3792	0	540 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2011 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/23/2011 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3568' - pumped 140 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1921' - pumped 115 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 30 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 15 sxs 60/40 pozmix - 4% gel.  
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3678	3680		
3661	3664		
3651	3657		
3571	3584		

RECEIVED  
AUG 29 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38158.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

AUG 25 2011