

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20458-00-00
Spot: NWNW Sec/Twnshp/Rge: 16-25S-17W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HORNBAKER Well #: 1
County: EDWARDS Total Vertical Depth: 4563 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD. PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4400		WITH 2 SX CMT
SURF	8.625	384		WITH 250 SX CMT
PROD	4.5	4538	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/05/2011 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP & 2 SX CMT. RUN TBG TO 1100'. FILL 4 1/2" & 4 1/2" X 85/8" ANNULUS WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2011 3:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG SET CIBP@ 4400' WITH 2 SX CMT. 2ND PLUG PERFORATE 4 1/2" AT 1100'. PUMPED 315 SX CMT. LOST CIRCULATION. WAIT ON CMT 2 1/2 HOURS. PUMPED 100 SX CMT. NO RETURNS. 3RD PLUG TOC IN 4 1/2" & 8 5/8" WAS 165'. FILLED BOTH WITH 3.5 YARDS OF REDI-MIX.

Perfs:

Top	Bot	Thru	Comments
4435	4439		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
AUG 29 2011
KCC WICHITA

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

AUG 25 2011

KCC DODGE CITY