

1091057

TO: STATE CORPORATION COMMISSION

API NUMBER 15-171-20,544-0000
E/2 SE SE SEC. 2, T 18 S, R 32 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CARPENTER TRUST "D" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT

OPERATOR LICENSE # 5123

WELL TOTAL DEPTH 4631 FEET

OPERATOR: PICKRELL DRILLING COMPANY

PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 110 N MARKET, SUITE 205

SURFACE CASING: SIZE 8 5/8" @ 260 ' WITH SX

ADDRESS WICHITA, KS 67202

CONDUCTOR CSG: SIZE " @ '

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PICKRELL DRILLING CO., INC LICENSE NUMBER 5123

ADDRESS 110 N MARKET, SUITE 205, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 10:15 PM DAY: 10 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KERNS

(COMPANY NAME) PICKRELL DRILLING (PHONE) 316-262-8427

WERE:

1ST PLUG AT 2320' WITH 50 SX CEMENT. 2ND PLUG AT 1480' WITH 80 SX CEMENT. 3RD PLUG AT 700' WITH 40 SX CEMENT. 4TH PLUG AT 280' WITH 40 SX CEMENT. 5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. NO MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:15 AM DAY: 11 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2320' WITH 50 SX CEMENT. 2ND PLUG AT 1480' WITH 80 SX CEMENT. 3RD PLUG AT 700' WITH 40 SX CEMENT. 4TH PLUG AT 280' WITH 40 SX CEMENT. 5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. NO MOUSE HOLE.

RECEIVED
ST. CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL 1/4 FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

7-6-00
JUL 6 2000

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED

Michael J. [Signature]
(TECHNICIAN)

Conservation Division
Wichita, Kansas

FORM CP-2/3

[Handwritten initials]