

To: 1 040775  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,456-0000  
App. NE NW SE, SEC. 6, T 18 S, R 32 W X  
2310 feet from S section line  
1700 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 31251  
Operator: Wabash Energy Corporation  
Name & Address: P.O. Box 595  
Lawrenceville, IL 62439

Lease Name Krebs Well # 1  
County Scott 155.70  
Well Total Depth 4794 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 265.92'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241  
Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 10:30 p.m. Day: 17 Month: 8 Year: 19 93

Plugging proposal received from Tom Alm  
(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2312-37'  
1st plug at 2340' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,  
3rd plug at 750' with 50 sx cement, 4th plug at 290' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 1 a.m. Day: 18 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2340' with 50 sx cement,  
2nd plug at 1500' with 80 sx cement,  
3rd plug at 750' with 50 sx cement,  
4th plug at 290' with 50 sx cement, 5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-23-93  
AUG 23 1993

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (XXXX) did not observe this plugging.  
DATE 8-24-93  
INV. NO. 38416

Signed Stephen J. Pfeifer (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas