

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 171-20,496-0000
SW SE , SEC. 6, T 18 S, R 32 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 31251

Lease Name Krebs Well # 2
County Scott 155.84
Well Total Depth 4795 feet

Operator: Wabash Energy Corporation
Name & Address: P.O. Box 595
Lawrenceville, IL 62439

Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: Day: 22 Month: 1 Year: 1996

Plugging proposal received from Tony Martin
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2321-41'
1st plug at 2340' with 50 sx cement, 2nd plug at 1500' with 100 sx cement,
3rd plug at 720' with 40 sx cement, 4th plug at 330' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORP COM
1996 JAN 28
1-26-96

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 22 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 2340' with 50 sx cement,
2nd plug at 1500' with 80 sx cement,
3rd plug at 720' with 40 sx cement,
4th plug at 330' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

did not observe this plugging.
1-30-96
44758
1-22

Signed Steve Durrant
(TECHNICIAN)