

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22195-00-00  
Spot: NWSW Sec/Twnshp/Rge: 27-20S-21W  
2022 feet from S Section Line, 650 feet from W Section Line  
Lease Name: HINNERGARDT Well #: 2-27  
County: NESS Total Vertical Depth: 4465 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	621		WITH 285 SX CMT
PC		1408		
PROD	5.5	4465	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2011 10:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: SAND TO 4315' & 5 SX CMT. PLUG AT 1460' WITH 15 SX GEL & 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/23/2011 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4260' WITH 5 SX CMT. LOAD HOLE WITH 15 SX GEL. 1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED. TIED ONTO BACKSIDE & PUMPED 2 SX CMT. PRESSURED TO 250#.

Perfs:

Top	Bot	Thru	Comments
4392	4397		

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED  
AUG 31 2011

KCC WICHITA

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED

AUG 25 2011

KCC DODGE CITY

Form CD 2/3

9/06/11