

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22094-00-00
Spot: NWNENE Sec/Twnshp/Rge: 5-26S-11W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: RUNDELL Well #: 10
County: PRATT Total Vertical Depth: 4320 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	244		WITH 265 SX CMT
PROD	5.5	4204	1918	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2011 10:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3950' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 08/19/2011 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 3950' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4064	4126		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
AUG 31 2011
KCC WICHITA

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
AUG 25 2011
KCC DODGE CITY

Form CR-23
9/06/11