

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22305-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 19-17S-28W
600 feet from S Section Line, 1731 feet from E Section Line
Lease Name: PENKA Well #: 1-19
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/21/2011 5:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: JOHN ARBRUSTER Company: DUKE DRILLING CO., INC. Phone: (316)267-1331

Proposed Plugging Method: 1ST PLUG AT 2140' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 08/21/2011 7:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2140' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED
AUG 31 2011
KCC WICHITA

District: 01

RECEIVED
AUG 25 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-102
9/06/11