

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20965-00-00  
Spot: N2NENE Sec/Twnshp/Rge: 11-30S-25W  
4780 feet from S Section Line, 660 feet from E Section Line  
Lease Name: ROONEY Well #: 1  
County: CLARK Total Vertical Depth: 5450 feet

Operator License No.: 5303  
Op Name: CANADAY OIL CORPORATION  
Address: 842 TOH-N-HAH TR  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1100		WITH 450 SX CMT
PROD	4.5	5448	2303	WITH 110 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2011 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 5230' WITH 4 SX CMT. PLUG AT 1550' WITH 10 SX GEL & 50 SX CMT. PLUG AT 1130' WITH 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2011 12:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED BACK TO 5230' WITH 4 SX CMT. 1ST PLUG AT 1550' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 1130' WITH 50 SX CMT. 3RD PLUG AT 280' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5389	5393		
5299	5311		
5276	5282		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

RECEIVED  
AUG 31 2011

KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
AUG 25 2011  
KCC DODGE CITY

Form CP-20  
9/6/11