

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-011-01199-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 2-24S-21E
1235 feet from S Section Line, 5125 feet from E Section Line
Lease Name: STEWART Well #: 1
County: BOURBON Total Vertical Depth: 740 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		5 SX
PROD	2	740		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2011 12:00 AM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: JASON KENT Company: _____ Phone: (785) 448-4101

Proposed Plugging Method: HOOK ON TO 2" AND PUMP WELL FULL.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed 06/07/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside 2" casing that was inside 10" surface casing to 700'. Circulated cement through 1" pipe inside 2" casing from TD to surface. Pulled 1" pipe. Ran 1" pipe inside the 10" casing on the backside of the 2" casing to 250'. Circulated cement throught the 1" pipe inside the 10" casing from 250' to surface. Pulled 1" pipe. Filled displacement. A total of 102 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
SEP 01 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)