

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19806-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 9-34S-12E
5105 feet from S Section Line, 2465 feet from E Section Line
Lease Name: CARTER B Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 1207 feet

Operator License No.: 30851
Op Name: CARTER, CALVIN GENE
Address: 1072 RD 26
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	300		40 SX
PROD	4.5	1224		125 SX

Well Type: EOR UIC Docket No: E24766.1 Date/Time to Plug: 05/25/2011 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: Phone: (620) 242-2519

Proposed Plugging Method: SRUN 1" TO TD. GEL HOLE SPOT 5 SKS PULL UP TO 800' SPOT 5 SKS PULL UP TO 350. CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 05/25/2011 10:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1090' gelled hole and spotted 5 sack plug. Pulled 1" up to 800' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well.

RECEIVED
JUN 30 DAS
KCC Chanute Dist. #3

Perfs:

Top	Bot	Thru	Comments
1168	1180		
RECEIVED SEP 01 2011 KCC WICHITA			

Remarks: WELL PLUGGED DUE TO FAILED MIT

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)