

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22413-00-01
Spot: E2SWNWSE Sec/Twnshp/Rge: 18-16S-14W
1650 feet from S Section Line, 2205 feet from E Section Line
Lease Name: NUSS A OWWO Well #: 1
County: BARTON Total Vertical Depth: 3445 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	327	0	250 SX
PROD	4.5	3444	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2011 3:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (785) 793-5838

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2011 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Junk in the well at 400'. Drilled down to 930' to anhydrite will plug there.
Ran tubing to 930' - pumped 40 sxs cement.
Pulled to 580' - pumped 70 sxs cement - circulated casing to surface.
Closed in casing - pumped 70 sxs - circulated surface pipe.
Pulled tubing - topped off with 15 sxs cement.

Perfs:

RECEIVED
SEP 02 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

9/06/11

AUG 25 2011