

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25346-00-00  
Spot: SWNENESW Sec/Twnshp/Rge: 13-18S-14W  
2200 feet from S Section Line, 2040 feet from W Section Line  
Lease Name: MAULER Well #: 1-13  
County: BARTON Total Vertical Depth: 3490 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 445 UNION BOULEVARD SUITE 208  
LAKEWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	810	0	330 SX CMT
T1	2.375	3095		
PROD	4.5	3154	1080	w/100 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2011 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DIXON Company: SHELBY RESOURCES LLC Phone: (720) 274-4682

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/11/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3154' - pumped 50 sxs cement.  
Pulled tubing. Cut casing at 1080' - pumped 100 sxs cement.  
Pulled casing to 500' - pumped 75 sxs cement.  
Pulled casing to circulate cement to surface with 70 sxs cement.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3022	3026		

RECEIVED  
SEP 02 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37150.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

9/06/11

AUG 25 2011