

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20816-00-00  
Spot: NESESENW Sec/Twnshp/Rge: 12-10S-33W  
2000 feet from N Section Line, 2615 feet from W Section Line  
Lease Name: WIELAND UNIT 12 Well #: 1  
County: THOMAS Total Vertical Depth: 2601 feet

Operator License No.: 34158  
Op Name: O'BRIEN RESOURCES, LLC  
Address: PO BOX 6149  
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	346		

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2011 12:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: JAY Company: O'BRIEN RESOURCES, LLC Phone: (318) 865-8568

Proposed Plugging Method: Ordered 180 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 08/28/2011 6:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Shot drill pipe off at 1601' w/100 sxs.  
2nd. Plug at 400' w/40 sxs.  
3rd. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Left 10 drill collars and bit in the hole at 2358'.

RECEIVED  
SEP 02 2011  
KCC WICHITA

Remarks: CONSOLIDATED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Case Morris  
(TECHNICIAN)

CM

Form CP-2/3

9/06/11

AUG 31 2011