

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-199-20,214-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR VESS OIL CORPORATION KCC LICENSE # 5030

ADDRESS 8100 E. 22nd St. North, Bldg. 300 CITY Wichita (operator's)

STATE Kansas ZIP CODE 67226 CONTACT PHONE # (316) 682-1537

LEASE Hibbert WELL# 1-33 SEC. 33 T. 14S R. 42 (East/West)

Approx. W/2-SE-SE SW SPOT LOCATION/QQQQ COUNTY Wallace

330' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2150' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH Common - 100 sx SACKS

SURFACE CASING SIZE 8 5/8" SET AT 693' CEMENTED WITH 60-40 pos. - 225 SACKS

PRODUCTION CASING SIZE            SET AT            CEMENTED WITH            SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:           

ELEVATION 3858'-3863' T.D. 5230' PETD            ANHYDRITE DEPTH             
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2825' w/25 sx; 2nd plug @ 1900' w/100 sx; 3rd plug @ 740' w/40 sx; 4th plug @ 40' w/10 sx; rathole 15 sx, Total 190 sx 60-40 posmix 6% gel 8 sx w/ celloflake.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? No

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

RECEIVED  
STATE CORPORATION COMMISSION  
03-29-1994  
MAR 29 1994

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# ( )            CONSERVATION DIVISION  
Wichita, Kansas

ADDRESS Sands Motel 622 W. Oklahoma City/State Ulysses, KS 67880

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

ADDRESS 150 N. Main, Suite 801 (company name) PHONE # (316) 262-1841 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) 5:00 p.m. 3-8-94 (complete)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-28-94 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)