

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-199-20023-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR RME PETROLEUM CO. KCC LICENSE # 6417
(owner/company name) (operator's)
ADDRESS 1201 Lake Robbins Drive CITY The Woodlands
STATE Texas ZIP CODE 77380 CONTACT PHONE (832) 636-1000
LEASE Johannes WELL# 1 SEC. 18 T. 15S R. 42W (xxxx/West)

C - NE - - SPOT LOCATION/QQQQ COUNTY Wallace
1320 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)
1320 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET#
CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS
SURFACE CASING SIZE 13 3/8" SET AT 564' CEMENTED WITH 475 SACKS
PRODUCTION CASING SIZE 4 1/2" SET AT 5248' CEMENTED WITH 410 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: Perfs 5112' - 5116'
ELEVATION 3922' / 3940' T.D. 5248' PBDT 5202' ANHYDRITE DEPTH 2828'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE
PROPOSED METHOD OF PLUGGING Set CIBP @ 5090' w/2sks CMT on top. Load hole w/9# gel to bottom of anhydrite @ 2828'. Pump 60/40 poz mix plug from 2828' - surface inside production casing. Pump 75 sacks plug in surface casing.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? N/A IS ACO-1 FILED? YES

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Herschel Kennedy PHONE# (719) 767-3401
ADDRESS 15562 Highway 385 City/State Cheyenne Wells, CO 80810

PLUGGING CONTRACTOR Eastern Colorado Well Service KCC LICENSE # 32997
(company name) (contractor's)
ADDRESS 43400 Hwy 40 Cheyenne Wells, CO 80810 PHONE # 719-765-5100

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) AUGUST 1, 2003

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/6/03 AUTHORIZED OPERATOR/AGENT: [Signature]

RECEIVED
AUG 12 2003
KCC WICHITA



15-199-20023-00-00

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko E & P Company LP
1201 Lake Robbins Drive
The Woodlands, TX 77380

August 13, 2003

Re: JOHANNES #1
API 15-199-20023-00-00
NE 18-15S-42W, 1320 FNL 1320 FEL
WALLACE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550