

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-199-20,215-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR VESS OIL CORPORATION KCC LICENSE # 5030  
(owner/company name) (operator's)

ADDRESS 8100 E. 22nd St. North, Bldg. 300 CITY Wichita

STATE Kansas ZIP CODE 67226 CONTACT PHONE # 316 682-1537

LEASE Walker Trust WELL# 1-2 SEC. 2 T. 15S R. 42 (East West)

- E/2 - SE - SE SPOT LOCATION/QQQQ COUNTY Wallace

500' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 706 CEMENTED WITH Lite - w/250 sx SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 1838'-1843' T.D. 5200 PETD \_\_\_\_\_ ANHYDRITE DEPTH 2804'-2832'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2820' w/25 sx; 2nd plug @ 1790' w/100 sx; 3rd plug @ 760' w/40 sx; 4th plug @ 40' w/10 sx; rathole 15 sx. Total 190 sx 60-40 posmix 68 gel 2 sx celloflake.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? No

If not explain why? sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# 316 743-5654

ADDRESS P.O. Box 103 City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # \_\_\_\_\_  
(company name) (contract #)

ADDRESS 150 N. Main, Ste 801, Wichita, KS 67202 PHONE # 316 262-1841 STATE CORPORATION COMMISSION

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Complete @ 6:00 a.m. 2-25-94 **MAR 03 1994**

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-2-94 AUTHORIZED OPERATOR/AGENT: [Signature] CONSERVATION DIVISION  
(signature) Wichita Kansas