

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 175-20940 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date \_\_\_\_\_.

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549  
(Owner / Company Name) (Operator's)

Address: 1201 Lake Robbins Drive City: The Woodlands

State: TX Zip Code: 77380 Contact Phone: ( 832 ) 636 - 3128

Lease: Etzold Unit North Well #: 3-6 Sec. 22 Twp. 33 S. R. 34  East  West

CSW Spot Location / QQQQ County: Seward

1320 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

3960 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # E-24960  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 1635' Cemented with: 775 Sacks

Production Casing Size: 5-1/2" Set at: 6424' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 6237'-6301'

Elevation: 2896' ( G.L. /  K.B.) T.D.: 6425' PBDT: 6340' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Dump 2 sxs hulls and 25 sxs cement to plug from 6340' to 6140'. RU jacks and shoot off 5-1/2" casing at +/- 1800'. Spot 50 sxs cement from 1685' to 1535'. Spot 50 sxs cement from 700' to 550'. Spot 15 sxs cement from 40' to 4'. Cut off and cap 8-5/8" casing 4' below surface.

RECEIVED  
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

SEP 30 2003

If not explain why? Logs submitted with original completion report.

CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Releford

Phone: ( 620 ) 482 - 1000

Address: 1707 W. 2nd City / State: Liberal, KS 67901

Plugging Contractor: Sargent & Horton Plugging, Inc. KCC License #: 31151  
(Company Name) (Contractor's)

Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: ( 405 ) 854 - 6515

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9-29-03 Authorized Operator / Agent: Jerry N. Blossom / Jerry N. Blossom  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

October 01, 2003

Re: ETZOLD UNIT NORTH #3-6  
API 15-175-20940-00-00  
SW 22-33S-34W, 1320 FSL 3960 FEL  
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888