

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

1-28
API NUMBER 15-071-20,677-00-00
445' FSL & 1176' FEL
SW SE SE, SEC. 14, T 16 S, R 42 WXX

TECHNICIAN'S PLUGGING REPORT

Operator License # 7873

Operator: Ricks Exploration Company
Name & Address: 5600 N. May Ave., Ste. 350
Oklahoma City, OK 73112

445 feet from S section line
1176 feet from E section line

Lease Name Carnes Well # 14A

County Greeley 177.84

Well Total Depth 5472 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 9 a.m. Day: 28 Month: 1 Year: 19 98

Plugging proposal received from Butch Heck

(company name) Ricks Exploration Company (phone) 800-960-9099

Perfs: 5 1/2" at 5445' w/225 sx cement, PBSD 5403', DV @ 1856' w/225 sx cement

Perfs at 5120-5222, CIBP at 5100' w/20' cement, cement retainer at 4977' w/30 sx cement,

Perfs at 4982-88, 4967-70'

1st plug pump 200 lbs. hulls and 25 sx cement with 100 lbs. hulls mixed in, 20 sx gel, and 215 sx cement. Check backside.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 28 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT

1st plug pumped 200 lbs. hulls, 25 sx cement with 100 lbs. hulls mixed in, 20 sx gel, and 215 sx cement. Maximum pressure 1000 psi and shut in 750 psi.

Pressured up 8 5/8" X 5 1/2" annulus to 500#.

IFPR 5
02-05-98

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

INVOICED

I (did / observe this plugging.

DATE 2-9-98

WV. NO. 50041

Signed Kevin P Strube (TECHNICIAN)