

239R

To: 1 070984
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,546-0000
NW NE NW, SEC. 14, T. 16, S, R. 42 W/E.
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30775
Operator: Savant Resources, Inc.
Name & Address: 216 16th St., Suite 1250
Denver, CO 80202

Lease Name Schurr Well # 1-14
County Greeley 167.86
Well Total Depth 5165 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 10 p.m. Day: 19 Month: 9 Year: 19 91

Plugging proposal received from Hugh Harvey
(company name) Savant Resources, Inc. (phone) 303-623-0070

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2717-47'
1st plug at 2750' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,
3rd plug at 400' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:45 a.m. Day: 20 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2759' with 50 sx cement,
2nd plug at 1511' with 80 sx cement,
3rd plug at 405' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 25 sx cement,
6th plug to circulate mousehole with 25 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 03 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

INVOICED
DATE 10-16-91
INV. NO. 33363

FOR KCC USE:

EFFECTIVE DATE: 8-25-91

DISTRICT #

SGAT Yes No

State of Kansas 071-20,546-00-00

NOTICE OF INTENTION TO DRILL

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 1 1991
month day year

Spot NW NE NW Sec 14 Twp 16 S. Rg 42 East West

OPERATOR: License # 30775
Name: Savant Resources, Inc.
Address: 216 16th Street, Suite 1250
City/State/Zip: Denver, Colorado 80202
Contact Person: Patterson Shaw
Phone: 303-592-1905

330 feet from South /North/line of Section
1650 feet from East /West/line of Section
IS SECTION REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Greeley

CONTRACTOR: License #: UNKNOWN AT THIS TIME
Name: UNKNOWN AT THIS TIME

Lease Name: Schurr Well #: 1-14
Field Name: Wildcat

Is this a Prorated/Spaced Field? ... yes no
Target Formation(s): Morrow, Spergen

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal Wildcat ... Cable
... Seismic: ... # of Holes ... Other
Other

Nearest lease or unit boundary: 330
Ground Surface Elevation: 3802 feet MSL

Water well within one-quarter mile: ... yes no
Public water supply well within one mile: ... yes no

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Depth to bottom of fresh water: 250
Depth to bottom of usable water: 1900

Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 350

Length of Conductor pipe required: None
Projected Total Depth: 5400

Formation at Total Depth: Spergen
Water Source for Drilling Operations:
... well farm pond ... other

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, true vertical depth:
Bottom Hole Location:

DWR Permit #: 240' Alt. IT Req.
Will Cores Be Taken?: ... yes no
If yes, proposed zone:

Exp. 2/20/92

AFFIDAVIT *Alt 2 completion only*

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Alvare Bell
SPUD DATE 9-11-91 INIT. YMK
LENGTH SURFACE PLANNED 360'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbls. when done bbbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 370' CONDUCTOR
ANHYDRITE T- 2717' B- 2747' ELEVATION

TD 5165' FORMATION Keyes
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 2750 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1500 Ft. W/ 80 SX

1/2, 1/2 Plug @ 705 Ft. W/ SX
3 Bottom Surface @ 400 Ft. W/ 50 SX
4 40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN DATE Hauling

TYPE OF CEMENT 60/40 per 59c
STARTING TIME : (AM/PM) DATE
COMPLETION TIME 12 : 45 (AM/PM) DATE 9-20-
CEMENT COMPANY Hall