

To: 1 080114 3-26
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 071-20,547-0000

N/2 NW NW, SEC. 14, T 16 S, R 42 W/X
4950 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Sell Well # 3

Operator: BEREXCO, Inc.

County Greeley 170.63

Name & Address P.O. Box 723

Well Total Depth 5250 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor BEREXCO, Inc. License Number 5363

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 2:45 p.m. Day: 26 Month: 3 Year: 19 97

Plugging proposal received from Mark Leiker

(company name) BEREXCO, Inc. (phone) 913-628-6101

Core: 5 1/2" at 5249' w/250 sx cement. PBD 5155', Perfs at 5075-79', DV @ 1994' w/440 sx cmt.

Plug through tubing: Tubing & rods in hole at 4117'

1st plug pump 25 sx cement, 50 lbs. hulls, 17 sx gel,

2nd plug pull tubing to 2000' and circulate to surface with 175 sx.

Check backside.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 7:30 p.m. Day: 26 Month: 3 Year: 1997

ACTUAL PLUGGING REPORT Hembree & Sons Well Service ran tubing to 4100'

1st plug pumped 15 sx gel, 25 sx cement, and 200 lbs. hulls,

2nd plug pulled tubing to 2000' and pumped 200 sx cement, circulated,

3rd plug pulled tubing and topped off with 25 sx cement.

4th plug went down 8 5/8" X 5 1/2" and pumped 3. sx cement. Pressured to 500 psi.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I do hereby acknowledge and approve this plugging.

DATE 4-2-97

INV. NO. 47842

Signed Kevin D. Thibault (TECHNICIAN)

04-02-97
2
0
11:00 AM