

1031126

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,531-00-00

NW NW SE, SEC. 11, T 16 S, R 42 W/E XX

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3882

Lease Name Voyager Well # 1-11

Operator: Samuel Gary Jr. & Associates, Inc.

County Greeley 169.00

Name & Address: 1775 Sherman Street, Suite 1925  
Denver, CO 80203

Well Total Depth 5200 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Norseman Drilling, Inc. License Number 3779

Address 200 E. 1st, Wichita, KS 67202

Company to plug at: Hour: 12 a.m. Day: 11 Month: 12 Year: 19 90

Plugging proposal received from Jim Riley

(company name) Norseman Drilling, Inc. (phone) 316-265-9408

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2690-2735'

1st plug at 2700' with 50 sx cement, 2nd plug at 1600' with 80 sx cement,

3rd plug at 960' with 50 sx cement, 4th plug at 410' with 50 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:30 a.m. Day: 11 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement;

2nd plug at 1600' with 80 sx cement,

3rd plug at 960' with 50 sx cement,

4th plug at 410' with 50 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy of report) observe this plugging.

DATE JAN 09 1990

Signed Steve Durrant (TECHNICIAN)

INV. NO. 30416

12-11

EFFECTIVE DATE: 11-25-90

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas  
NOTICE OF INTENTION TO DRILL

071-20,531-0000

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 30 1990  
month day year

NW NW SE Sec 11 Twp 16 S, Rg 42 East  West

OPERATOR: License # 3882  
Name: Samuel Gary Jr. & Associates, Inc.  
Address: 1775 Sherman Street, Suite 1925  
City/State/Zip: Denver, Colorado 80203  
Contact Person: Dan Hall  
Phone: (303) 831-4673 or (303) 832-8013

2,310 feet from South line of Section  
2,310 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 03779  
Name: Norseman Drilling, Inc. Rig #1

County: Greeley  
Lease Name: Voyager Well #: 1-11  
Field Name: UNNAMED  
Is this a Prorated Field? yes  no   
Target Formation(s): Morrow  
Nearest lease or unit boundary: 330 ft.  
Ground Surface Elevation: 3786.69 feet MSL  
Domestic well within 330 feet: yes  no   
Municipal well within one mile: yes  no   
Depth to bottom of fresh water: 900 ft. 125  
Depth to bottom of usable water: 1300 ft. 125  
Surface Pipe by Alternate: 1  2  
Length of Surface Pipe Planned to be set: 350 ft.  
Length of Conductor pipe required: N/A  
Projected Total Depth: 5,200'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations: (existing irrigation)  well  farm pond  other   
DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken? yes  no   
If yes, proposed zone: \_\_\_\_\_

Well Drilled For: Well Class: Type Equipment:  
 Oil  Inj  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OAWO  Disposal  Wildcat  Cable  
 Seismic;  # of Holes

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? yes  no   
If yes, total depth location: \_\_\_\_\_

Exp. 5/20/91

AFFIDAVIT

RECEIVED  
STATE OF KANSAS  
340' Alt. Well Reg.  
JUL 21 1990  
U.S.A. 55-101

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the provisions of the Kansas Conservation Act, Chapter 55-101, et. seq.

Pusher ? Jim Ailey  
SFUD DATE 11-30-90 INIT.  
LENGTH SURFACE PLANNED \_\_\_\_\_  
RESERVE PIT STATUS- REMOVE FLUID \_\_\_\_\_ LINED \_\_\_\_\_  
after salt sect. no bbls. when done bbls.  
RATHOLED AHEAD? Y N \_\_\_\_\_ SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 7/8 @ 38.5 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- 2690 B- 2735 ELEVATION \_\_\_\_\_  
TD 5200 FORMATION MISS  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
1 Anhydrite Base @ 2700 Ft. W/ 50 SX  
2 1/2 Base Anhy. @ 1600 Ft. W/ 80 Flow SX  
3 1/2, 1/2 Plug @ 960 Ft. W/ 50 Flow SX  
4 Bottom Surface @ 410 Ft. W/ 50 SX  
5 40' Plug @ 40-0 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
TECHNICIAN S.D. DATE 12-9-90 Hauling \_\_\_\_\_  
TYPE OF CEMENT 60/40 Patmix 6% gnl.  
STARTING TIME 12:00 (AM/PM) DATE 12-11-90  
COMPLETION TIME 3:30 (AM/PM) DATE 12-11-90  
CEMENT COMPANY Allied