

1080215

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,549-00-00
NW SE SW SEC. 11, T 16 S, R 42 W

10-1

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME YOUNG WELL # 2-11

TECHNICIAN'S PLUGGING REPORT COUNTY GREELEY 168.68

OPERATOR LICENSE # 5152 WELL TOTAL DEPTH 5190 FEET

OPERATOR: BANKS OIL COMPANY PRODUCTION CSG: SIZE 4 1/2 " FEET 5188

NAME AND ADDRESS 200 W DOUGLAS, STE 550 SURFACE CASING: SIZE 8 5/8 " FEET 355'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING CO. LICENSE NUMBER 5418

ADDRESS PO BOX 1389, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 01 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MAX BALL

(COMPANY NAME) ALLIED CEMENTING CO. (PHONE) 316-793-5681

WERE: PERFS AT 5064-69 (F.O. TOOL @ 1902' WITH 475 SX CEMENT)

PUMP DOWN 8 5/8" X 4 1/2" ANNULAS PRESSURE UP TO 500#. PUMP DOWN 4 1/2" WITH 200# HULLS, 40 SX CEMENT WITH 100# HULLS MIXED IN, 15 SX GEL. PUMP 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 01 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

PUMPED DOWN 8 5/8" X 4 1/2" ANNULAS PRESSURED UP TO 500#, PUMPED DOWN 4 1/2" 200# HULLS, 40 SX CEMENT WITH 100# HULLS MIXED IN, 15 SX GEL. PUMPED 100 SX CEMENT. MAXIMUM PSI PRESSURE AT 1700#. SHUT IN @ 1700#. (CEMENT FROM 1750' TO SURFACE IN 4 1/2" CASING.)

10-14-98
RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1998

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P. Strube
(TECHNICIAN) FORM CP-2/3

10-15-98
60113
C