

MAR 12 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,434-00-00

SW NE SW, SEC. 8, T 16 S, R 42 W EX

1820 feet from S section line

3530 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4034

Lease Name M.K. White Well # 1

Operator: Remuda Corporation

County Greeley 172.25

Name & Address P.O. Box 7127

Well Total Depth 5300 feet

Billings, MT 59103-7127

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 12:30 a.m. Day: 12 Month: 3 Year: 19 87

Plugging proposal received from Bill Reiter

(company name) Murfin Drilling Company (phone) 913-687-5123

Elevation 3852'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2705-49'

1st plug at Base Stone Corral with 50 sx cement, 2nd plug at 1850' with 80 sx cement,

3rd plug at 30' below base of surface pipe with 40 sx cement,

4th plug at 0-40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 a.m. Day: 12 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2745' with 50 sx cement,

2nd plug at 1850' with 80 sx cement,

3rd plug at 335' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If you do not observe this plugging.)

Signed J. A. [Signature]
(TECHNICIAN)

Rec'd
MAR 12 1987
Kee

[Handwritten initials]

DATE _____

INV. NO. 3-12

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date Feb. 20, 1987 month day year

API Number 15- 071-20,434-00-00

OPERATOR: License # KCC 4034 Name Remuda Corporation Address P.O. Box 7127 City/State/Zip Billings, MT 59103-7127 Contact Person Norm Brown Phone 303-830-0331

SW NE SW Sec. 8 Twp 16 S, Rg. 42 W West 1820 Ft. from South Line of Section 3530 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # KCC 6033 Name Murfin Drilling Co. City/State Wichita, Kansas

Nearest lease or unit boundary line 820 feet County Greeley

Lease Name M.K. White Well # 1 Ground surface elevation 3848 feet MSL

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext. Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Surface pipe by Alternate: 1 X

Depth to bottom of fresh water 240

Depth to bottom of usable water 1750

Surface pipe planned to be set 300

Projected Total Depth 5250 feet

Formation Morrow

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Production casing will be cemented in, upon completion of well from below usable water to surface.

Date 2-12-87 Signature of Operator or Agent Edward F. Drilling Title Vice-President

For KCC Use: Conductor Pipe Required 300 feet; Minimum Surface Pipe Required 300 feet per Alt. This Authorization Expires 8-17-87 Approved By 2-17-87

SPUD 3-4-87

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth (feet), plug size (sxs), and plug material (e.g., 60% Poz., 6% gel). Includes entries for 1st through 5th plugs and Rathole/Mousehole.

Log table with columns: Pusher, TD, Surface Pipe, Anhydrite, Starting Time & Date, Completion Time & Date, 1st-4th Plug @, Rat Hole Circulated W/, Mouse Hole Circulated W/, Water Well Plugged W/, Cement Company, Technician.

STATE COMMISSION CONSERVATION DIVISION Wichita, Kansas