

DEC 4 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,405-60-00

NW NW NE, SEC. 7, T 16 S, R 42 W 22 Ex

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9228

Lease Name Archie Well # 1

Operator: Marlin Oil Corporation
Name & Address: 2700 First National Center
Oklahoma City, OK 73102

County Greeley 172.74

Well Total Depth 5315 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 500

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 11:00 a.m. Day: 4 Month: 12 Year: 1986

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-8179

were: 4 1/2" at 5313' PBT 4508' Perfs at 4433-38'

1st plug pump bottom 1 sx hulls, 20 sx cement,

2nd plug spot through casing at 1670' with 50 sx cement,

3rd plug spot through casing at 550' with 50 sx cement,

4th plug spot through casing at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 4 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT Drill mud between plugs and 35 bbls. ahead of 1st plug,

1st plug pump 1 sx hulls and 20 sx common cement, spot plugs through casing -

2nd plug at 1670' with 50 sx cement,

3rd plug at 550' with 50 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

DEC 10 1986

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used common cement by Sargent's.

(If additional description is necessary, use BACK of this form.)

INVOICED
I will / serve this plugging.

DATE 12-10-86

Signed Dan Dodson (TECHNICIAN)

155.89