

1 060364

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,365 -00 00
NW SW NW, SEC. 7, T 16 S, R 42 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum, Inc.
Name & Address 300 West Douglas, Suite 800
Wichita, KS 67202

3630 feet from S section line

4950 feet from E section line

Lease Name Garvey, Inc. 'P' Well # 5

County Greeley

Well Total Depth 5300 (St. Genevieve) 17225 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1739

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 4:00 am Day: 11 Month: May Year: 19 85

Plugging proposal received from Bill Daugherty

(company name) Cheyenne (phone) 316-277-2062
Elevation 3882

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2770-80'

1st plug at 2775' with 50 sx cement

2nd plug at 1760' with 50 sx cement

3rd plug at 880' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 am Day: 11 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2775' with 50 sx cement, 2nd plug at 1760' with 50 sx

cement, 3rd plug at 880' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
05-21-85
MAY 21 1985

Remarks: Used 60/40 Pozmix 2% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

(did / did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 5-21-85

INV. NO. 8222