

1060118

TO: STATE CORPORATION COMMISSION

9-3

API NUMBER 15-071-20,314 - 00-00
C SW NE SEC. 7, T 16 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 960 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2210 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HALE WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 172.90

OPERATOR LICENSE # 9228

WELL TOTAL DEPTH 5320 FEET

OPERATOR: MARLIN OIL CORPORATION

PRODUCTION CSG: SIZE 4 1/2 " FEET 5275

NAME AND PO BOX 14630

SURFACE CASING: SIZE 8 5/8" FEET 510'

ADDRESS OKLAHOMA CITY, OK 73113

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING CO LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 03 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM W.R. LYNN

(COMPANY NAME) ALLIED (PHONE) 316-793-5861

WERE: PERFS AT 4168-70, 4222-24, 4285-90, 4554-57, 5114-26

50 SX CEMENT WITH 200# HULLS THEN WIPER PLUG. THEN 10 SX GEL FOLLOWED BY 160 SX CEMENT.

09-10-98

RECEIVED
SAS CORP
SEP 10 A 11:48

PLUGGING PROPOSAL RECEIVED BY MIKE MATERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 7:00 PM DAY: 03 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

PUMPED 50 SX CEMENT WITH 200# HULLS AND THEN WIPER PLUG. THEN 10 SX GEL FOLLOWED BY 160 SX CEMENT. IT WENT ON VACUUM. PUMPED ANOTHER 100 SX CEMENT STILL ON VACUUM. PUMPED DOWN BACK SIDE PRESSURED TO 500# AND HELD. LATER THAT AFTERNOON, PUMPED ANOTHER 320 SX CEMENT BEFORE CEMENT STAYED AT SURFACE.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED
HAS BEEN 2 STAGED FROM 1826' TO 200' WITH 400 SX CEMENT

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Mares (TECHNICIAN) FORM CP-2/3

DATE 9-11-98

INV. NO. 51298

9-3