

1
060439

API NUMBER 15-071-20,344-0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 7, T 16 S, R. 42 W/EX
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9228

Lease Name Waldo Well # 1
County Greeley 172.25

Operator: Marlin Oil Corporation
Name & Address 2700 First National Center
Oklahoma City, OK 73102

Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 514

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Gibson Drilling Company License Number 5866
Address Ft. Morgan, CO 80701

Company to plug at: Hour: noon Day: 17 Month: December Year: 19 84

Plugging proposal received from Dick Lynn
(company name) Marlin Oil Corporation (phone) 405-232-3267

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 5100' with 50 sx cement 2nd plug at 2740' with 50 sx cement
3rd plug at 1670' with 50 sx cement 4th plug at 560' with 50 sx cement
5th plug hulls - plug at 40' -- cement to surface with 10 sx cement
7th plug to circulate rat hole with 10 sx cement
8th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Paul D. Luther
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 1:30 pm Day: 17 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 5100' with 50 sx cement, 2nd plug at 2740' with 50
sx cement, 3rd plug at 1670' with 50 sx cement, 4th plug at 560' with 50 sx cement,
5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10
sx cement, 7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate
mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 02 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of form.)

I (did / did not) observe this plugging.
1-16-85
6530

Signed Paul D. Luther
(TECHNICIAN)