

1 95 1 1 5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW NW NW, SEC. 5, T 16 S, R 42 (W)K
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,386-00-00

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7506

Lease Name Sloan Well # 11-5 (40)

Operator: First Energy Corporation

County Greeley 169.55 (Mississippi)

Name & Address 16701 Greenspoint Park Dt, St.200

Well Total Depth 5217 feet

Houston, TX 77060

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 474

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 22 Month: August Year: 19 85

Plugging proposal received from Ed McKinney

(company name) Murfin (phone) 316-267-3241

Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2710'

1st plug at 2715' with 50 sx cement 2nd plug at 1750' with 50 sx cement

3rd plug at 850' with 50 sx cement 4th plug at 480' with 40 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 10 sx cement

8th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30 pm Day: 22 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2715' with 50 sx cement, 2nd plug at 1750' with 50 sx cement, 3rd plug at 850' with 50 sx cement, 4th plug at 480' with 40 sx cement,

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate mouse hole

with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

(If not observed) observe + STATE CORPORATION COMMISSION

DATE _____

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 9819

AUG 28 1985