

1 0-0650

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,403 -00-00

C SW NW, SEC. 5, T 16 S, R 42 W XX

3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7506

Lease Name Sloan Well # 12(40)5

Operator: First Energy Corporation

County Greeley

Name & Address 16701 Greenpoint Park Drive

Well Total Depth 5250 Mississippi 170.63 feet

Houston, TX 77760

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 9:00 pm Day: 29 Month: October Year: 19 85

Plugging proposal received from Wally Towns

(company name) Abercrombie Drilling (phone) 316-262-1841
Elevation 3732

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2740

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1770' with 80 sx cement

3rd plug 30' below the base of the Surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10
sx cement Plugging Proposal Received by Steve Durrant

Plug water well from bottom to top with cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 am Day: 30 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2740' with 50 sx cement, 2nd plug at 1770' with 80
sx cement, 3rd plug at 540' with 20 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugged water well
from bottom to top with cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

Signed Richard W. Lacey
TECHNICIAN

NOV 4 1985

NOV 1 1985

DATE NOV 4 1985

CONSERVATION DIVISION

INV. NO. 10879 / 0-30 Wichita, Kansas