

1 4

24 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-071-20,430-00-00
NW SE NE, SEC. 5, T 16 S, R 42 W/E
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7506

Lease Name Sloan Well # 73-5
County Greeley 171.28

Operator: First Energy Corporation
Name & Address: 16701 Grdenspoint Park Dr., St. 200
Houston, TX 77060

Well Total Depth 5270 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 514

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 7 Month: 11 Year: 19 86

Plugging proposal received from Matt Finnesy

(company name) Murfin Drilling Company (phone) 913-386-4453

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3831'
Anhydrite 2714-51'

1st plug at 2715' with 50 sx cement, 2nd plug at 1750' with 50 sx cement;
3rd plug at 850' with 50 sx cement, 4th plug at 480' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 10 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2 a.m. Day: 8 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement,
2nd plug at 1680' with 70 sx cement, 3rd plug at 990' with 50 sx cement,
4th plug at 540' with 40 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 10 sx cement,
7th plug to circulate mousehole with 10 sx cement.

rcw
11-12-86
NOV 12 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 11-12-86

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 15339 05 1986

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Date 10 31 86 month day year 2:30

API Number 15- 071-20,430-00-00 2
NW SE NE Sec. 5 Twp. 16 S, Rg. 42 East
3630 Ft. from South Line of Section
990 Ft. from East Line of Section

OPERATOR: License # 7506
Name First Energy Corporation
Address 16701 Grdenspoint Park Dr., St. 200
City/State/Zip Houston, TX 77060

Contact Person Bill Dean
Phone 713-875-5755

CONTRACTOR: License # 6033
Name Murfin Drilling Company
City/State Wichita, KS

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildrat Cable

if OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 10-29-86 Signature of Operator or Agent Jack E. Guss; Agent for Title Ass't. Drilling Manager

or KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 450 feet per Alt. #2

This Authorization Expires 4-29-87 Approved By 10-29-86

Move in 10-31-86 set 500' surface pipe
NW. SE. NE. Sec. 5... Twp. 16... S, Rg. 42... East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 4 p.m. workdays).

Table with columns for plug depth, size, and material. Includes rows for 1st, 2nd, 3rd, 4th plugs and a mousehole.

Vertical list of well parameters: PUSHED Matt - Zimey, TD 5320 FORMATION Muds, SURFACE PIPE 8 7/8 @ 514, ANHYDRITE 2714 ELEVATION 3931, STARTING TIME & DATE 11:00pm 11-7-86, COMPLETION TIME & DATE 2:00am 11-8-86, 1st PLUG @ 2700 FT. W/ 50 SX, 2nd PLUG @ 1680 FT. W/ 70 SX, 3rd PLUG @ 980 FT. W/ 50 SX, 4th PLUG @ 540 FT. W/ 40 SX, RAT HOLE CIRCULATED W/ 10 SX, MOUSE HOLE CIRCULATED W/ 10 SX, WATER WELL PLUGGED W/ New Water, CEMENT COMPANY Halliburton, W. Sekend / S. West, TECHNICIAN 11-10-86-DG

NOV 12 1986