

1090968

TO: STATE CORPORATION COMMISSION

10-25

API NUMBER 15-071-20,695-00-00
60'W OF SW SE SE SEC. 2, T 16 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1050 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SELL WELL # 1-2

TECHNICIAN'S PLUGGING REPORT COUNTY GREELEY 167.38

OPERATOR LICENSE # 03581 WELL TOTAL DEPTH 5150 FEET

OPERATOR: RED OAK ENERGY, INC PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 783140 SURFACE CASING: SIZE 8 5/8" FEET 352'

ADDRESS WICHITA, KS 67278

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING CO. LICENSE NUMBER 30606

ADDRESS 250 N WATER, STE. 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 25 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM GUS SCHWARTZ

(COMPANY NAME) MURFIN DRILLING CO (PHONE) 316-267-3241

WERE:

1ST PLUG AT 2720' WITH 50 SX CEMENT, 2ND PLUG AT 1000' WITH 80 SX CEMENT,

3RD PLUG AT 380' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 25 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2720' WITH 50 SX CEMENT, 2ND PLUG AT 1000' WITH 80 SX CEMENT,

3RD PLUG AT 380' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/2# FLOSEAL BY ALLIED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

11-23-98 60367 10-25

RAWZ