

R

146 R

to: 1 031201
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,564-00-00
SE SE NW, SEC. 1, T 16 S, R 42 W/4
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5152

Operator: Lee Banks, d/b/a Banks Oil Co.
Name & Address 200 W. Douglas, Suite 550
Wichita, KS 67202

Lease Name Wimberly Well # 1
County Greeley
Well Total Depth 5250 170.62 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606
Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 1 Month: 7 Year: 19 92

Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2705-32'

1st plug at 2700' with 50 sx cement, 2nd plug at 1950' with 80 sx cement,
3rd plug at 1000' with 50 sx cement, 4th plug at 370' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10

sx cement, Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 a.m. Day: 2 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2700' with 50 sx cement,
2nd plug at 1950' with 80 sx cement,
3rd plug at 1000' with 50 sx cement,
4th plug at 370' with 40 sx cement,
5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Steve Durrant (TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION JUL 8 1992
CONSERVATION DIVISION Wichita, Kansas

35840

EFFECTIVE DATE: 6-23-92
DISTRICT #
SSA? Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL (5-071-20,564-00-00) ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date June 22, 1992
month day year

Spot
V.C. SE. SE. NW. Sec 1... Twp 16... S. Rg. 42. X West

OPERATOR: License # 05152 ✓
Name: Lee Banks, d/b/a Banks Oil Co.
Address: 200 W. Douglas, Suite 550
City/State/Zip: Wichita, Kansas 67202
Contact Person: Lee Banks
Phone: 316-267-0783

2970 feet from South ~~North~~ line of Section
2970 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # 30606 ✓
Name: Murfin Drilling Co., Inc.

(NOTE: Locate well on the Section Plat on Reverse Side
County: Greeley
Lease Name: Wimberly Well #: 1
Field Name: wildcat
Is this a Prorated/Spaced Field? yes X no
Target Formation(s) Morrow-Mississippi
Nearest lease or unit boundary: 330
Ground Surface Elevation: 377.1 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 290
Depth to bottom of usable water: 1950
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 340
Length of Conductor pipe required: 0
Projected Total Depth: 5250
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well ... farm pond X ... other
DUR Permit #: ...
Will Cores Be Taken? yes X no
If yes, proposed zone: ...

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield .X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal .X Wildcat ... Cable
... Seismic; ... # of Holes ... Other
If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth
Directional, Deviated or Horizontal wellbore? yes no
If yes, true vertical depth:
Bottom Hole Location:

AFFIDAVIT

310' Alt. II Req.

Exp. 12/18/92

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55 101, et. seq.
It is agreed that the following minimum requirements will be met:

Notify the appropriate district office prior to spudding a well;

Pusher Robert S. ...
SPUD DATE 6-24-92 INIT. CM
LENGTH SURFACE PLANNED 340'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 340 CONDUCTOR
ANHYDRITE T-2705 B-2732 ELEVATION
TD 5250 FORMATION M.S.S.
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 3700 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1950 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 1300 Ft. W/ 50 SX
4 Bottom Surface @ 370 Ft. W/ 40 SX
5 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W 5 SX MOUSE HOLE W/10 SX

WATER WELL Yes SX (Irr. Well Pond
Hauling
TECHNICIAN SD DATE 7-1-92
TYPE OF CEMENT 60/40 6%
STARTING TIME (AM/PM) DATE 7-1
COMPLETION TIME (AM/PM) DATE 7-2-92
CEMENT COMPANY Allied
STATE CORPORATION COMMISSION
Wichita, Kansas
DIVISION
8
1992

Ed McKenna