

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-053-20594-00-00

LEASE NAME Albina Zalondek

WELL NUMBER 1-17

SPOT LOCATION C E/2 SW/4

SEC. 17 TWP. 14 SRGE. 10 (E) or (W) (W)

COUNTY Ellsworth

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-24-86

Plugging Completed 5-12-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling Bought F/Davies & Company,  
Inc.

ADDRESS P.O. Box 347 Chase, Kansas 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 2285'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	460'	none
				4-1/2"	2284'	1077'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Plugged off bottom with sand to 2045' and 4 sacks cement. Shot pipe @1077' and pulled a total of 27 joints of 4-1/2" casing. Plugged surface with 3 hulls and 100 sacks econolite w/2 hulls.  
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1986

My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1986  
05-16-86  
CONSERVATION DIVISION  
Wichita, Kansas

15-053-20594-00-00

PROPERTY MANAGEMENT  
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS  
RE-COMPLETIONS

**LEITH OPERATIONS, INC.**

427 UNION CENTER BLDG.  
WICHITA, KANSAS 67202  
TELEPHONE 316-265-3491

DAVIES & COMPANY, INC.  
4501 E. 31st. Suite 101  
Tulsa, Oklahoma 74135

ALBINA ZALOUEK WELL NO. 1-17  
C E/2 SW/4 Sec. 17-14S-10W  
Ellsworth County, Kansas

CASING RECORD

July 14, 1980

Ran, set and cemented 57 jts. 2289' 4 1/2" OD 9.5# 8rd. R-3, Smls casing @ 2289' (1' off total depth) Cemented w/ 150 sacks common cement 10% salt - Plug down 4:15 AM 7-14-80.

Shoe joint 40.27' long - float @ 2248'.

Centralizers - 2248', 2208', 2168', 2087' and 495'.

Good returns at surface during cementing.

Directions: Wilson - 1 1/2 miles East.

PROPERTY MANAGEMENT  
LEASE OPERATIONS

A SERVICE OF THE OIL INDUSTRY

WELL COMPLETIONS  
RE-COMPLETIONS

**LEITH OPERATIONS, INC.**

427 UNION CENTER BLDG.  
WICHITA, KANSAS 67202  
TELEPHONE 316-265-3491

DAVIES & COMPANY, INC.  
4501 East 31st. St. - Suite 101  
Tulsa, Oklahoma 74135

ALBINA ZALOUEK WELL NO. 1-17  
C E/2 SW/4 Sec. 17-14S-10W  
Ellsworth County, Kansas

COMPLETION RECORD

SUMMARY:

PBTD 2237'

Perforations: 2118-22 & 2095-2102'

Stimulation: Fracture: 46,000# Sand

Tubing: 67 jts. 2083' - 2-3/8" OD EUE 8rd. and 2 jts 2145

Seating Nipple: 2-3/8" x 12"

1/2 E of Center Union B+  
No ord 40 - No to low.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 3 1986

CONSERVATION DIVISION  
Wichita, Kansas

71-466  
TO 2285