

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-199-20104 -00-00

LEASE NAME Arapahoe Unit

WELL NUMBER 115

4950 Ft. from N Section Line

800 Ft. from W Section Line

SEC. 1 TWP. 15S RGE. 43 (E) or (W)

COUNTY Wallace

Date Well Completed _____

Plugging Commenced 03/12/98

Plugging Completed 03/12/98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Union Pacific Resources Company

ADDRESS PO Box 7, MS 3006 Fort Worth, Texas 76101

PHONE# (817) 877-7809 OPERATORS LICENSE NO. 06417

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 27, 1998 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Morrow Depth to Top 5140' Bottom 5160' T.O. 5299'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	Surface	425'	8 5/8"	7187	NA
		Surface	5299	4 1/2"	7187	NA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Mix & Spot gel spacer w/ 200# Hulls @ 5050'. Backfilled. TOOH w/ 66 Jts tbq. EOT @ 2866'. Mix. Spotted & balanced 335 sxs 60/40 POZ w/ 10% gel cement w/ Hulls from 2866' to surface. TOOH w/ remaining 91 jts. tbq. R.U. to surface valve. Pumped 25 sxs. pressured up to 500 psi. Capped off production casing w/ 40 sxs to surface. R.D., cut-off 5' below surface, cap well. Backfill & cleanup location.

Name of Plugging Contractor Allied Cementers License No. _____

Address PO Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources Company RCWD

STATE OF Texas COUNTY OF Tarrant, ss. 03-18-98

Brian W. Davis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 7, MS 3006 Fort Worth, Texas 76101

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 98

Lisa D. Winburne
 Notary Public

