

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-199-20110-00-00

LEASE NAME Akers D

WELL NUMBER #1

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 17 TWP. 15S RGE. 42 (E) or (W)

COUNTY Wallace

Date Well Completed 9/21/87

Plugging Commenced 9/30/99

Plugging Completed 10/4/99

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Mull Drilling Company, Inc.

ADDRESS P.O. Box 2758 Wichita KS 67201-2758

PHONE# (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Gas

(Oil, Gas, O&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 9/30/99 (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 5096 Bottom 5108 T.D. 5350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Gas &amp; Water</u>	<u>5096</u>	<u>5108</u>	<u>5 1/2"</u>	<u>5338'</u>	<u>None</u>
				<u>8 5/8"</u>	<u>716'</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
9/30/99: Dumped 2 bbls sand (120') over perms 5096'-5108'. Tagged top of sand @ 4996'. Set 5 sack cement plug on top of sand from 4996' to 4865'. Tagged top of cmt between 8 5/8" and 5 1/2" casing at 58'. Pumped 10 sacks cement down 8 5/8"-5 1/2" annulus. Pumped 10 sacks cement followed by 25 sacks w/1000# hulls and tailed in with 155 sacks cement to place plug from  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Pipe & Salvage, Inc. License No. 15288

Address P.O. Box 467 Chase KS 67524-0467

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Mark A. Shreve, President of Mull Drilling Co., Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 2758 Wichita KS 67201-2758

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 99

**TANNIS L. TRITT**  
 Notary Public - State of Kansas  
 My Appt. Expires 3-26-2003

Commission Expires: \_\_\_\_\_

March 26, 2003

Notary Public

CONTINUED:

3400' to surface. ISIP 200#. SI.

10/4/99: Cut off casing below surface, welded on cap and restored location.