

STATE, OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-199-20,215-0000

LEASE NAME Walker Trust

WELL NUMBER #1-2

500 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 15S RGE. 42 (E) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd St. North, Bldg. 300, Wichita, KS 67226 COUNTY Wallace

PHONE/(316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed _____

Character of Well D&A

Plugging Commenced 2-24-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-25-94

The plugging proposal was approved on 2-25-94 (date)

by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 5200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	706'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud: set 1st plug @ 2820'-2720' w/25 sx; 2nd plug @ 1790'-1390' w/100 sx; 3rd plug @ 760'-600' w/40 sx; 4th plug @ 40'-surface w/10 sx; rathole 15 sx; Total 190 sx 60-40 posmix 6% gel 2 sx celoflake.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.


Mark R. Galyon

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Mark R. Galyon

(Address) 150 N. Main, Ste 801, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 94

Charles Standard
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAR 03 1994

My Commission Expires: March 20, 1997

USE ONLY ONE SIDE OF EACH FORM

CONSERVATION DIVISION
Wichita, Kansas