

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-071-206430000

LEASE NAME Chance Heirs

WELL NUMBER 1

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 23 TWP. 16 RGE. 40 XXIor (W)

COUNTY Greeley

Date Well Completed Drilled April, 1996

Plugging Commenced April 7, 2000

Plugging Completed April 7, 2000

RECEIVED
04-12-2000
APR 12 2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR HB Operating, Inc.

ADDRESS c/o Rob Williams, Agent, PO Box 15163, Amarillo, TX 79105

PHONE (806) 374-4555 OPERATORS LICENSE NO. 31916

Character of Well Dry Hole

(Oil, Gas, O&A SWD, Input, Water Supply Well)

The plugging proposal was approved on April 7, 2000 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Log was attached to CP-1

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 3045'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
See Attached		0	258	8-5/8	258	0
		0	3050	4-1/2	3050	0
				(Top Cement @ 790')		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

See Attached

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address PO Box 466, Ness City, Kansas 67560


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rob Williams, Agent

STATE OF Texas COUNTY OF Potter, ss.

Rob Williams, Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Rob Williams

(Address) P.O. Box 15163, Amarillo, TX 79105



AND SWORN TO before me this 10th day of April, 2000

Linda K. McKean
Notary Public

My Commission Expires: _____



15-071-20643-0000

CHANCE HEIRS #1
1320' FSL & 1320' FWL
23-16S-40W
GREELEY COUNTY, KANSAS

PERFORATING & PLUGGING RECORD

Perforated Towanda: 2942'-2960'
Perforated Ft. Riley: 2968'-2977'
Result: Water
Set CIBP @ 2938' with 2 sacks cement on top.

Perforated Winfield: 2875'-2922'
Result: Water
Set CIBP @ 2800' with 2 sacks cement on top.

Perforated Cheyenne: 1538'-1540'
Result: Water
Set CIBP @ 1490' with 2 sacks cement on top.

Perforated 4-1/2" casing @ 780' (2 holes) & pumped 200 sacks
cement down 4-1/2" casing, circulated cement to surface.

RECEIVED
STATE OF KANSAS COMMISSION

APR 12 2000

CONSERVATION DIVISION
Wichita, Kansas