


15-071-20142-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Greeley County, Sec. 21 Twp. 16 Rge. 40 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C. SE $\frac{1}{4}$
Lease Owner ONE Drilling Inc.
Lease Name Mackay - Hixon "A" Well No. 1
Office Address 515 R.H. Garvey Bldg., Wichita, Kans.
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Gas



Locate well correctly on above
Section Plot

Date Well completed, June 26 19 77
Application for plugging filed August 1, 19 77
Application for plugging approved August 5, 19 77
Plugging commenced August 8, 19 77
Plugging completed August 10, 19 77
Reason for abandonment of well or producing formation _____
Non commercial Value
If a producing well is abandoned, date of last production _____
None 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Balthazor
Producing formation Hugoton Depth to top 2975' Bottom 3017' Total Depth of Well 3096'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	289'	0'
Production				5 1/2"	3096'	1749'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 2 Sacks bulls & 10 sacks cement to 2820' Pressured to 750 lbs
Pumped 25 sacks cement 900' to 825'
Mud 825' to 285'
Pumped 25 sacks cement 285' to 210'
Mud 210' to 40'
Put bridge & 10 sacks cement 40' to 0'.

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1977
08-06-7977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling
Box F, Sublette, Kansas 67877 Kans. Permit # 766

STATE OF KANSAS COUNTY OF Haskell, ss.
I Edgar J. Eves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Kansas 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1977

Sandra L. Eves
Notary Public.

My commission expires 12-6-80



15-071-20142-00-00

DRILLERS' LOG

D N B DRILLING, INC.
No. 1 Mackay-Hixon
C SE Sec. 21-16S-40W
Greeley County, Kansas

Commenced: 6-23-77
Completed: 6-27-77

Surface Casing: 281' of 8-5/8"
cemented w/250 sx common, 3% cc
6-23-77

FORMATION

DEPTH

Surface Hole	0 - 289
Shale	289 - 1744
Shale & Sand	1744 - 2095
Shale	2095 - 3297 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.
Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 4th day of August, 1977.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1977
08-16-1977
CONSERVATION DIVISION
Wichita, Kansas