

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

APR NUMBER 15-071-20,680-00-00

LEASE NAME Lobmeyer

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-33

2310 Ft. from <sup>N</sup> Section Line

2330 Ft. from <sup>W</sup> Section Line

SEC. 33 TWP. 17S RGE. 42 (E) or (W)

LEASE OPERATOR Red Oak Energy, Inc.

COUNTY Greeley

ADDRESS 200 W. Douglas, Suite #510

Date Well Completed 10-09-97

PHONE#(316) 265-9925 OPERATORS LICENSE NO. 03581

Plugging Commenced 10-07-97

Character of Well D/A

Plugging Completed 10-09-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-07-97 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Enclosed if not, is well log attached? RECORDED

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O.

KANSAS CORPORATION COMMISSION  
T.O.

Show depth and thickness of all water, oil and gas formations.

DEC 16 1997  
12-16-1997

OIL, GAS OR WATER RECORDS

CASING RECORD

CONSERVATION DIVISION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Fill with heavy mud. 1st plug from 2650'-2450' with 50 sks, 2nd plug from 1700'-1380' with 80 sks, 3rd plug from 800'-640' with 40 sks, 4th plug from 300'-100' with 50 sks, 5th plug from 40'-0' with 10 sks, 15 sks in rat hole. Cemented with 245 sks 60/40 pos, 6% gel, 1/4# floeal per sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF Kansas COUNTY OF Sedgwick, ss.

KEVIN DAVIS

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kevin Davis

(Address) 200 W. Douglas, Wichita, 67202

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 97

Victoria Davis  
Notary Public



Expires: October 21, 2001