

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20763-00-00
Spot: W2NENESW Sec/Twnshp/Rge: 23-16S-42W
2300 feet from S Section Line, 2150 feet from W Section Line
Lease Name: HIBBERT-CARNES Well #: 1
County: GREELEY Total Vertical Depth: 5178 feet

Operator License No.: 33259
Op Name: ARROW OIL & GAS, INC.
Address: PO BOX 722347
NORMAN, OK 73070

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4900		WITH 2 SX CMT
CIBP		5030		
SURF	8.625	356		WITH 250 SX CMT
PROD	5.5	5172	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2011 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TRACEY HOLLIS Company: ARROW OIL & GAS Phone: (405) 364-2601

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2011 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****PERFORATED AT 2756' & 1520' & CEMENTED TO 0' WITH 1075 SX CMT.** CIBP @ 4900'. FL @ 3550'. 1ST PLUG AT 2700' WITH 25 SX CMT. SPACER TO 2000'. 2ND PLUG AT 2000' WITH 50 SX CMT. SPACER TO 400'. 3RD PLUG 50 SX CMT FROM 400' TO 0'. HOLE STAYED FULL. COULD NOT PUMP INTO ANNULUS. FULL OF CMT.**

Perfs:

Top	Bot	Thru	Comments
5054	5064		
5050	5053		
4971	4975		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
AUG 25 2011
KCC DODGE CITY

Signed: Ken Jehlik

(TECHNICIAN)
RECEIVED
SEP 13 2011
KCC WICHITA

Form CP-2/3

9/14/11