

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20395-00-00
Spot: SWSW Sec/Twnshp/Rge: 35-30S-41W
683 feet from S Section Line, 4579 feet from E Section Line
Lease Name: JOHNS A Well #: 1-35
County: STANTON Total Vertical Depth: 5800 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5380		WITH 2 SX CMT
SURF	8.625	1565		WITH 750 SX CMT
PROD	5.5	5792	1570	WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/30/2011 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: DAVID N. PAULY Company: C.H. TODD Phone: (316) 721-2020

Proposed Plugging Method: SET CIBP @ 5380' WITH 2 SX CMT. SHOOT 5 1/2" CASING & POH. RIH W/TBG TO 1600' & PUMP 50 SX CMT. PIH TO 600' & PUMP 50 SX CMT. POH TO 60' & FILL TO SURFACE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2011 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5380' WITH 2 SX CMT. SHOOT 5 1/2" CASING AT 1570' & POH. 1ST PLUG RIH W/TBG TO 1600' & PUMP 50 SX CMT. 2ND PLUG POH TO 600' & PUMP 50 SX CMT. 3RD PLUG POH TO 60' & FILL TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5425	5434		KEYES

Remarks: USED 60/40 POMIX 4% GEL BY CONSOLIDATED CEMENTERS.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
SEP 13 2011
KCC WICHITA

Form CP223

9/14/11