

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20379-00-00
Spot: SESE Sec/Twnshp/Rge: 33-30S-41W
680 feet from S Section Line, 645 feet from E Section Line
Lease Name: LAWSON Well #: 1
County: STANTON Total Vertical Depth: 5650 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1554		WITH 75 SX CMT
PROD	5.5	5649	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2011 1:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DAVID N. PAULY Company: C.H TODD Phone: (316) 721-2020

Proposed Plugging Method: PUMP 50 SX CMT W/200# HULLS AT 5400'. PERFORATE 5 1/2" CASING AT 1600' & PUMP 75 SX CMT. PEROFRATE 5 1/2" CASING AT 550' & PUMP 50 SX CMT. FILL CASING TO SURFACE FROM 60'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: PARTIAL
Date/Time Plugging Completed: 08/30/2011 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 50 SX CMT & 200# HULLS @ 5400'. UNABLE TO SHOOT & POH WITH 5 1/2" CASING. PEFORATE 5 1/2" CASING AT 1608', PUMPED 75 SX CMT WITH FLUID CIRCULATION TO SURFACE. PERFORATE 5 1/2" CASING AT 550'. PUMPED 150 SX CMT CIRCULATING CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5442	5650		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED WELL SERVI CE.

Plugged through: CSG

RECEIVED

SEP 13 2011

KCC WICHITA

District: 01

Signed

Jack L Maclosky
(TECHNICIAN)

RECEIVED

SEP - 7 2011

KCC DODGE CITY

Form OP-2/3

9/14/11