

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-22302-00-00  
Spot: SENESE Sec/Twnshp/Rge: 26-16S-30W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SHAY DIRREEN B Well #: 1  
County: LANE Total Vertical Depth: 4560 feet

Operator License No.: 6009  
Op Name: DOUBLE EAGLE EXPLORATION, INC.  
Address: 800 W 47TH ST STE 318  
KANSAS CITY, MO 64112

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 387        |             | WITH 250 SX CMT |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2011 2:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.  
Proposal Rcvd. from: DAVE YOTT Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: 1ST PLUG AT 2300' WITH 50 SX CMT. 2ND PLUG AT 1480' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 08/25/2011 6:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 2300' WITH 50 SX CMT. 2ND PLUG AT 1480' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED  
SEP 13 2011  
KCC WICHITA

District: 01

RECEIVED

AUG 25 2011

KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)

Form 8023

9/14/11