

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21061-00-00
Spot: NWSEENW Sec/Twnshp/Rge: 14-29S-18W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: UNRUH Well #: 2-B
County: KIOWA Total Vertical Depth: 5006 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3500		WITH 2 SX CMT
CIBP		4900		WITH 2 SX CMT
SURF	8.625	620		WITH 400 SX CMT
PROD	4.5	5039	0	WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/01/2011 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB LLC Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 4900' WITH 2 SX CMT. CIBP @ 3500' WITH 2 SX CMT. TEST CASING THEN PERFORATE @ 1175' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2011 2:40 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4900' WITH 2 SX CMT. SET CIBP @ 3500' WITH 2 SX CMT. PRESSURED CASING TO 300#. PERFORATED AT 1175' & PUMPED 200 SX CMT THROUGH CASING WITH SLIGHT BLOW. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
4978			
4944			
3638			
3632			
3530			
3528			

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
SEP 13 2011

KCC WICHITA

District: 01

RECEIVED
SEP - 8 2011
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-2/3
9/14/11